

## Construction sequences of Jetty

- **Step 1: Piling work**



- **Step 2: Installation of formwork and casting pile cap's concrete**



- **Step 3:** Installation of reinforcement and casting concrete of transverse and longitudinal beam



- **Step 4:** Installation of precast slab



- **Step 5:** Installation of reinforcement and casting of topping concrete



- **Step 6:** Installation of facilities on Jetty



- **Step 7: Completion**

